



SPECIFICATIONS

Request for Tender (RFT)	Spray Seal Works
Closing Time:	25.08.2017
RFT Number:	001-17.18



1 INTRODUCTION

Request for tender to undertake **all or part** of Councils Town Spray Sealing program as directed,

Current road projects for 2017 / 2018 include,

- 6240 m2 in Elliston township
- 2870 m2 in Lock township
- 15661 m2 in Port Kenny Township
- 5848 m2 in Venus Bay Township
- 72000 m2 on the Mt Wedge to Kyancutta Road

2 BACKGROUND INFORMATION

Tender prices are required for the following items,

1. Supply of 7mm Grey-stone, per tonne
2. Supply of 10mm Grey-stone, per tonne
3. Supply of 14mm Grey-stone per tonne
4. Delivery of 7mm, 10mm and 14mm Grey-stone, per tonne
5. Single coat re-seals, per m2
6. Two coat re-seals, per m2
7. Preparation Works/Minor Repair m2

3 SCOPE OF THE WORK

- Work-zone Traffic Management
- Site preparation street sweeping
- Protection of all man-hole covers, inspection points and fire water access points
- Protection of all road markers or delineators
- Supply and delivery of 7mm, 10mm and 14mm Grey-stone
- Dry-matting where required or directed
- Application rates to be determined at each location, site dependant
- Temporary reinstatement of regulatory Stop or Give Way line-marking where directed
- Site clean-up and removal of excess stone where directed

1 LOCK		
North Terrace	Heron to Terre & Terre to West Terrace	10 mm Seal
Starke Street	Palkagee St to West Terrace	10 mm Seal



2 ELLISTON

Kapara Road	Sixth Street to Seventh Street	10 mm Seal
Seventh Street	Wandana Road to Beach Terrace	7 mm Seal
Beach Terrace	Seventh Street to East Terrace	7 mm Seal
	Waterloo Bay Drive, Rupara Ct & Unnamed Street	10 mm Seal

3 PORT KENNY

Pygery Road	Chainage 2203 to 4576	10mm Seal

4 VENUS BAY

Venus Bay Road	Chainage 3000 to Ch 3860	10 mm seal

5 MT WEDGE

Mt Wedge to Kyancutta Road	Ch 8000 from Birdseye Highway to Ch 18000	2 Coat 14/7mm seal
----------------------------	---	--------------------

Preparation work/ Minor Repair work as Quoted.

6 SPECIFIC REQUIREMENTS OF THE CONTRACT

- All contractor staff to have appropriate Personal Protective Equipment, Training, and Plant licences/Tickets required to perform any part of this tender requirement.
- Work-zone traffic management accreditation is required as part of this tender
- Work Health Safety Policy
- Public Liability Insurance \$10 million
- Contract Works Insurance \$10 million
- All works will need to be completed by end of March 2018; The Principal reserves the right to accept a Tender in part or in whole



7 TIMETABLE FOR PROCUREMENT

Place Advertisement in Newspaper*	1.08.2017
Issue Request for Tender	1.08.2017
Closing Time*	Five(5)pm Friday 25.08.2017
Evaluation of Tender Responses*	01.09.2017
Submission to the Principal*	11.09.2017
Acceptance of Tender*	15.09.2017

**Dates are subject to alteration by the Principal in its discretion.*

8 IMPLEMENTATION TIMETABLE

Commencement date and proposed works schedule will be negotiated upon acceptance of tender with the Operations Manager and successful contractor or contractors. All works will need to be completed by end of March 2018. This will be dependent on the Construction of the Mt Wedge to Kyancutta Road, however this is anticipated to be completed well inside that timetable.